

T10/07-192r0

Proposal for 6G SAS Spec on Minimum TX V_{VMA}

Mike Jenkins
LSI Corp

Need for a min V_{VMA} Spec

- Current proposal includes normative limit for TX V_{PK-PK} (min & max)
- Current proposal for de-emphasis is *informative*, not normative
- Hence, there is no normative minimum value for V_{VMA} , although V_{VMA} is probably the most significant parameter from a signal integrity perspective

Proposal

- Establish V_{VMA} (min) spec at 600 mVppd

