


# SCSI USABLE BANDWIDTH

## Fixed Select Times; Varying Data Rate

T10/98-105 Rev 0  
 To: T10 Committee (SCSI)  
 From: George Penokie  
 Subject: SPI-3 Performance

MB/sec



- Overhead based on SCSI Fast-wide and Ultra SCSI measurements
- Assumption: overhead for Select, etc. remains constant; data clocking rate equals nominal rate
- Example uses 256 Block transfers, 48 Block max burst
- Environment: 1 initiator and 4 - 8 targets

Nominal Data Rate	Effective Data Rate	Effectv % of Nominal	Nom Rate vs Predecessor	Effective Rate vs Predecessor
20	18	88%		
40	31	78%	2X	1.72X
80	51	64%	2X	1.65X
160	74	46%	2X	1.45X